

KATHMANDU UNIVERSITY

Dhulikhel , Kavre



Kabeli-A Hydroelectric Project

Presented By:

Shrija Shrestha (027917-20)

Sarita Sapkota(028084-20)

Dharambir Yadav(028097-20)

Rajesh Yadav(028098-20)

Acknowledgement

We thank Kabeli Energy Ltd. subsidiary of BPC, and Arun Kabeli Power Ltd. for the internship opportunity at Kabeli-A HEP.

Special thanks to Mr. Sanjeev Neupane, Mr. Tulsi B. Khadka, Mr. Sumit Thapa, Mr Lakpa Sherpa, Mr Basanta Chaudhary, Mr Gopal Thapa and Mr. Abhinash Kayastha our on-site supervisors, and Asst. Prof Santosh Chaudhary our internal supervisor for their guidance throughout the intern period.

Gratitude to Kathmandu University, Department of Civil Engineering for their support throughout this journey.

Objectives

- To Gain practical exposure to hydropower construction and operations.
- To Understand project management and coordination in hydropower development.
- To Enhance problem-solving and technical skills through site experience.
- To Familiarize with key hydropower infrastructure components.

History

1. Location: Panchthar & Taplejung, Nepal
2. Capacity: 37.6 MW
3. Developer: Kabeli Energy Ltd. (KEL) and Butwal Power Company (BPC)
4. Initial Contractor: Zambala Construction Pvt Ltd, Paramax Constructions, Sherpa Hydro Constructions
5. Consultants: Units Engineering Consultancy
6. Commencement Date: Project development started in the early 2010s
7. Funding: Initially backed by the World Bank
8. Termination: The financial closure failed, leading to project termination



Fig 1 :Transmission Pole

Salient Features

S.N.	Item	Description
1	Project Name	Kabeli-A Hydroelectric Project
2	Location	Hilihang RM (Panchthar) & Pathivara/Yangbarak RM (Taplejung)
2.1	Project Boundaries	East: 87° 45' 50" E, West: 87° 40' 55" E, North: 27° 17' 32" N, South: 27° 13' 41" N
3	Type of Development	Run-of-River (Cascade RoR)
4	Hydrology at Intake	Catchment Area: 713.90 km ² , Mean Monthly Flow: 47.078 m ³ /s, 100-Year Flood: 1020 m ³ /s
5	Pipe from Phawa Khola to Tailwater Taping Canal	Surface, Mild Steel, Length: 200 m, Internal Diameter: 1.2 m, Thickness: 6-8 mm
6	Tailwater Taping Canal	RCC Pressurized Box Canal, Size: 4.2 m × 3.6 m, Length: 366 m
7	Approach Tunnel	Inverted D-shaped, Concrete Lined, Size: 68 m × 6.33 m × 4 m
8	Additional Intake	Side Intake, Size: 3.0 m × 1.5 m, Gate: Vertical Fixed Wheel

Salient Features

9	Additional Intake Approach Canal	RCC Box Culvert, Length: 265 m, Dimensions: 2.7 m × 3.5 m
10	Settling Basin	Simple Rectangular, Number of Chambers: 1, Dimensions: 55.0 m × 13.5 m × 10.4 m
11	Headrace Canal (Convey Chamber to Headpond)	RCC Box Culvert, Size: 4.25 m × 4.25 m, Slope: 1:700, Length: 1161 m
12	Head Pond	Rectangular Concrete Lined, Length: 55 m, Width: 8.0 m, Height: 8.9 m, Max Storage Volume: 3825 m ³
13	Headrace Canal (Head Pond to Inlet Portal)	RCC Pressurized Box Culvert, Size: 4.2 m × 4.2 m, Length: 33.0 m
14	Headrace Tunnel	Inverted D-shaped, Shotcrete & Concrete Lined, Length: 4657 m, Diameter: 5.65 m
15	Surge Shaft	Underground & Exposed to Surface, Internal Diameter: 12.0 - 12.9 m, Height: 55 m

Salient Features

16	Penstock	Material: Mild Steel, Length: 254 m before Trifurcation, Length of Each Leg: 80.75 m, Internal Diameter: 3.8 m
17	Powerhouse	Semi-Surface, Size: 58.80 m × 19.40 m × 28.50 m, Machine Floor Level: 465.00 masl
18	Tailrace	Design Tailwater Level: 458.0 masl, Length: 123 m, Cross-section: 5.5 m × 3.0 m
19	Turbine	Horizontal Axis Francis, Units: 3, Rated Speed: 600 rpm, Output: 12,930 kW each
20	Generator	Salient Pole Rotor Synchronous Generator, Units: 3, Voltage: 11 kV, Rated Capacity: 14,750 kVA
21	Transformer	Three Phase, Oil Immersed, Outdoor Core, Units: 3, Rated Capacity: 16.5 MVA
22	Power and Energy Output	Installed Capacity: 37.60 MW, Gross Head: 120.50 m, Estimated Annual Energy: 218.99 GWh

Salient Features

23	Transmission Line	Voltage: 132 kV, Length: Loop-in Loop-out with Kabeli Corridor Transmission Line
24	Access Road	To Headworks: 7.4 km, To Powerhouse: 15 km from Mechi Highway
25	Project Cost	Total Cost: NRs. 7520 million, Per MW Cost: NRs. 200 million
26	Financial Analysis	NPV: NRs. 10,290,000, B/C Ratio: 1.19, ROE: 15.55%, IRR: 12.75%

Location

Province : Province No. 1

Districts : Panchthar & Taplejung

River Basin : Kabeli River

Elevation : 450 m to 2000 m above sea level

Coordinates:

East: 87° 45' 50" E

West: 87° 40' 55" E

North: 27° 17' 32" N

South: 27° 13' 41" N




Fig 2 : Location of site

Source: Final DPR KAHEP Report

Geology

The project area lies in the Lesser Himalayan zone, mainly composed of granite with smaller amounts of phyllite, quartzite, gneiss, and schist from the Taplejung window. Granite dominates the headworks area, while the surge shaft and powerhouse areas consist of phyllite, schist, and quartzite. Foliation generally trends 30° – 40° northward.




Fig 3 : Geological map of Nepal

Hydrology

The total discharge required to obtain the installed capacity of 37.6 MW IS 37.73 m³/s. Out of this 35.1m³/s is obtained from Kabeli B1 Intake and the remaining 2.6m³/s is obtained from Phawa khola tailrace.




Fig 4: Catchment area of Kabeli River

Source: Final DPR KAHEP Report

Hydrology




Fig 5 : Flow duration curve of Kabeli B1
Source: Final DPR KAHEP Report

Project Components

Interconnection Conduit

- Transfers water from KB1HEP cascade tailrace to Headpond.
- 366m long RCC pressurized canal (4.2m x 3.6m).
- Design discharge: 37.23 m³/s,
- Velocity: 2.4 m/s.



Fig 6 : Interconnection Chamber

Additional Intake Gate

- Side intake with three orifices (3m x 1.5m each).
- Designed for 12 m³/s with 1 m/s velocity.
- Trash racks prevent debris; vertical gates control flow.



Fig 7 : Additional Intake Gate

Additional Intake Approach Canal

- 265m long
- RCC box canal (2.7m x 3.5m)
- Regulated by a vertical lift gate



Fig 8 : Approach Canal

Approach Tunnel

Excavated Dimensions: 7.15 m (W) × 5.25 m (H)

Rock Type: Type-IV and V

Lining Details:

- Concrete lining: 0.4 m thick (Invert, Wall, and Crown)
- Shotcrete: 10–15 cm thick (plain)
- Dividing wall thickness: 0.5 m



Fig 9 : Approach Tunnel

Settling Basin

- Removes sediments ($\geq 0.2\text{mm}$) to protect turbines.
- Single-bay, 55m long, 13.5m wide, 10.4m high.
- Flow velocity: 0.2 m/s, sediment flushing system included.



Fig 10 : Settling Basin

By Pass Gate

- Purpose: Maintenance of Headpond & Siphon
- Protection: Cutoff walls on both sides enhance stability.
- Risk: Long 1080 m headrace canal lacks breaking point, increasing failure risk.
- Benefit: Prevents canal collapse and ensures structural safety.



Fig 11 : By Pass Gate

Siphon

Purpose: Protect headrace canal from Khangrawa drainage (Kartikey Kholi) during rainy season.

Length: 50 meters.

Functions:

- Diverts canal flow beneath the drainage.
- Maintains continuous water flow using pressure flow.
- Prevents canal collapse during heavy rainfall.



Fig 12 : Siphon

Head Pond

- Mixes water from KB1HEP and Phawa Khola.
- 55m x 8m x 8.9m, holds 3825 m³ water.
- Fine trash rack (8m x 6.5m) prevents debris entry.



Fig 13: Head Pond

Spillway

- 40m long sharp-crested spillway.
- Discharges excess water back to Kabeli Khola (55 m³/s capacity).



Fig 14 :Spillway

Headrace Tunnel

- 4657m long, 5.65 m width and 5.65 m height, inverted D-shape.
- Shotcrete-lined for cost-efficiency, velocity: 1.35 m/s.



Fig 14 :Headrace Tunnel

Surge Tank

- Vertical cylindrical tank (55m high, 12.0–12.90m diameter).
- Connected to a 254m-long, 3.80m-diameter steel pressure pipe.

Water levels

Normal (El. 573.30 masl),

Max (El. 591.45 masl),

Min (El. 558.15 masl).



Fig 15 : Surge Tank

Steel Penstock Pipe

- 254m long
- Mild steel pipe
- Optimized at 3.8m diameter.
- Thickness: 12mm to 25mm.



Fig 16 : Bifurcation of Penstock

Powerhouse

- Semi-underground powerhouse on the right bank of Piple Khola, Hilihang Rural Municipality-2, Panchthar.
- Dimensions: 58.80m (L) × 19.40m (W) × 28.50m (H).
- Tailrace canal: 90.1m long, conveying water to Tamor River via RCC canal
- 5.5m × 3.0m, 123m-long conduit.
- Turbine center line: 459.65 masl, Service bay level: 465.0 masl.



Fig 17 : Powerhouse

Tailrace

- Three individual tailrace units of 17.60 meters each.
- These units handle the outflow of water from the turbines and lead it into the combined tailrace.
- The tailrace maintains water pondage between RL 452.18 msl and 446.85 msl to regulate the water level.



Fig 18 : Tailrace

Work Progress

Tunnel Failure at 1+703 m section

Chainage: 1+703 m

Invert/Ground Level: 557 masl / 1257 masl

Overburden: ~700 m

Cause: High overburden stress

Damage:

- 25 m tunnel section failed
- 17 steel ribs damaged
- Backhoe loader in failure zone (equipment risk)




Fig 19: Tunnel Failure

Tunnel Protection Measure

- Installed wire mesh as an immediate support
- Ongoing reinforcement in failed section
- Mucking Process (Failure Section): Ongoing for 2 months to ensure proper clearance.



Fig 20 : Mucking of Debris

Concreting

- Headworks: Intake concreting nearly done; settling basin in progress
- Penstock: Plum Concrete placement ongoing
- Powerhouse: Turbine & generator foundation work almost complete
- Tailrace: Tailrace near completion; pondage work pending




Fig 21 :Concreting

Reinforcement Placing

- Correct bar diameter, spacing, and layout as per structural drawings.
- Clean reinforcement (free from rust, oil, mud, etc.).
- Proper cover blocks used to maintain concrete cover.
- Bars securely tied using binding wire to prevent displacement during concreting.
- Overlap maintained properly.
- Hooks, bends, and anchorage as per design for proper stress transfer.



Fig 22 :Reinforcement Placing

Soling and PCC

- M10 grade is used for pcc

Things to be considered:

1. Surface Preparation
2. Compaction
3. Level and Slope
4. Thickness



Fig 23 : Soling

Soling and PCC

- **PCC**

1. M10 grade.
2. 10 cm thickness.
3. Reduces seepage and provides a smooth surface

- **Soiling**

1. 15 cm depth.
2. Provides base stabilization.



Fig 24 : PCC

Excavation for Cutoff Wall

The protection work around this structure is carried out using a cut-off wall to ensure safety against the river meandering process and the water pressure of the river having a width of 3.0 m and height of 6.8 m throughout the interconnected gate portion



Fig 25 : Excavation Work

Drilling and Blasting

The methods of Drilling and Blasting may vary depending on the quality and condition of the rock.

1. Drill pattern design
2. Drilling
3. Loading and Blasting
4. Ventilating
5. Mucking
6. Securing
7. Geological Mapping



Fig 26 : Arrangement for Blasting

A large red square with a white border, centered on a white background. Inside the square, the text "Project Activities" is written in white.

Project Activities

Conducting Tests

Cube test

28-day cube test of the concrete block 15*15*15 cm was carried out and the test generated a strength of 26 MPa for M25 concrete

Slump Cone Test

The slump cone test resulted in a 75 mm slump, indicating a true slump with good workability suitable for construction.

Conducting Tests



Fig 27 : Compressive Testing Machine



Fig 28 : Slump Cone Test

Zimbabwe Construction Pvt. Ltd.
Kwame N. Nkomo Building, Harare (ZIMBABWE)
Compressive Strength Test of Concrete

Test Results		Material Description	
Test No.	Test Date	Material Name	Batch No.
101	10/10/2018	Concrete	101
102	10/10/2018	Concrete	102
103	10/10/2018	Concrete	103
104	10/10/2018	Concrete	104
105	10/10/2018	Concrete	105
106	10/10/2018	Concrete	106
107	10/10/2018	Concrete	107
108	10/10/2018	Concrete	108
109	10/10/2018	Concrete	109
110	10/10/2018	Concrete	110
111	10/10/2018	Concrete	111
112	10/10/2018	Concrete	112
113	10/10/2018	Concrete	113
114	10/10/2018	Concrete	114
115	10/10/2018	Concrete	115
116	10/10/2018	Concrete	116
117	10/10/2018	Concrete	117
118	10/10/2018	Concrete	118
119	10/10/2018	Concrete	119
120	10/10/2018	Concrete	120
121	10/10/2018	Concrete	121
122	10/10/2018	Concrete	122
123	10/10/2018	Concrete	123
124	10/10/2018	Concrete	124
125	10/10/2018	Concrete	125
126	10/10/2018	Concrete	126
127	10/10/2018	Concrete	127
128	10/10/2018	Concrete	128
129	10/10/2018	Concrete	129
130	10/10/2018	Concrete	130
131	10/10/2018	Concrete	131
132	10/10/2018	Concrete	132
133	10/10/2018	Concrete	133
134	10/10/2018	Concrete	134
135	10/10/2018	Concrete	135
136	10/10/2018	Concrete	136
137	10/10/2018	Concrete	137
138	10/10/2018	Concrete	138
139	10/10/2018	Concrete	139
140	10/10/2018	Concrete	140
141	10/10/2018	Concrete	141
142	10/10/2018	Concrete	142
143	10/10/2018	Concrete	143
144	10/10/2018	Concrete	144
145	10/10/2018	Concrete	145
146	10/10/2018	Concrete	146
147	10/10/2018	Concrete	147
148	10/10/2018	Concrete	148
149	10/10/2018	Concrete	149
150	10/10/2018	Concrete	150
151	10/10/2018	Concrete	151
152	10/10/2018	Concrete	152
153	10/10/2018	Concrete	153
154	10/10/2018	Concrete	154
155	10/10/2018	Concrete	155
156	10/10/2018	Concrete	156
157	10/10/2018	Concrete	157
158	10/10/2018	Concrete	158
159	10/10/2018	Concrete	159
160	10/10/2018	Concrete	160
161	10/10/2018	Concrete	161
162	10/10/2018	Concrete	162
163	10/10/2018	Concrete	163
164	10/10/2018	Concrete	164
165	10/10/2018	Concrete	165
166	10/10/2018	Concrete	166
167	10/10/2018	Concrete	167
168	10/10/2018	Concrete	168
169	10/10/2018	Concrete	169
170	10/10/2018	Concrete	170
171	10/10/2018	Concrete	171
172	10/10/2018	Concrete	172
173	10/10/2018	Concrete	173
174	10/10/2018	Concrete	174
175	10/10/2018	Concrete	175
176	10/10/2018	Concrete	176
177	10/10/2018	Concrete	177
178	10/10/2018	Concrete	178
179	10/10/2018	Concrete	179
180	10/10/2018	Concrete	180
181	10/10/2018	Concrete	181
182	10/10/2018	Concrete	182
183	10/10/2018	Concrete	183
184	10/10/2018	Concrete	184
185	10/10/2018	Concrete	185
186	10/10/2018	Concrete	186
187	10/10/2018	Concrete	187
188	10/10/2018	Concrete	188
189	10/10/2018	Concrete	189
190	10/10/2018	Concrete	190
191	10/10/2018	Concrete	191
192	10/10/2018	Concrete	192
193	10/10/2018	Concrete	193
194	10/10/2018	Concrete	194
195	10/10/2018	Concrete	195
196	10/10/2018	Concrete	196
197	10/10/2018	Concrete	197
198	10/10/2018	Concrete	198
199	10/10/2018	Concrete	199
200	10/10/2018	Concrete	200

PA = 10 MPa
 $1 \times 10^6 \text{ N/m}^2 = 10^6 \times 10^{-2} \text{ N/m}^2 = 10^4 \text{ N/m}^2$

Signature: [Signature]
 Date: 10/10/2018

Fig 29 : Bar Bending Schedule Sheet

Quality Checks

Construction quality control was conducted by inspection to ensure compliance

1. Cover block presence checked.
2. Bar bending schedule reviewed.
3. Adequacy of lap length verified.
4. Formwork placement inspected.
5. Mix design quality ensured.



Fig 30 : Checking of cover blocks

Bar Bending Schedule

The bar bending schedule (BBS) was carried out to ensure that sufficient reinforcement availability for structural safety and integrity. It also served as a crucial reference for billing work, helping to verify the quantity of reinforcement used in the construction process.

Bottom main Bar (20d) - Rev 1

Bar No.	Dimensions	Length	Quantity
1	20L	324	120 x 1 = 359
2	20L	356	120 x 1 = 393
3	20L	332	120 x 1 = 427
4	20L	427	120 x 1 = 462
5	20L	467	120 x 1 = 496
6	20L	495	120 x 1 = 530
7	20L	516	120 x 1 = 551
8	20L	537	120 x 1 = 566
9	20L	547	120 x 1 = 576
10	20L	562	120 x 1 = 590
11	20L	573	120 x 1 = 591
12	20L	443	120 x 1 = 461
13	20L	413	120 x 1 = 431
14	20L	383	120 x 1 = 401
15	20L	353	120 x 1 = 371
16	20L	324	120 x 1 = 342
17	20L	294	120 x 1 = 312
18	20L	264	120 x 1 = 282
19	20L	234	120 x 1 = 253
20	20L	204	120 x 1 = 223
21	20L	175	120 x 1 = 193
22	20L	145	120 x 1 = 163
23	20L	110	120 x 1 = 128
24	20L	726	120 x 3 = 761
25	20L	714	120 x 3 = 747
26	20L	697	120 x 3 = 732
27	20L	685	120 x 3 = 720
28	20L	672	120 x 3 = 707
29	20L	660	120 x 3 = 695
30	20L	648	120 x 3 = 681
31	20L	635	120 x 3 = 671
32	20L	623	120 x 3 = 658
33	20L	611	120 x 3 = 646
34	20L	613	120 x 3 = 662
35	20L	618	120 x 3 = 636

Fig 31 : Bar Bending Schedule

Drawing Analysis

The observation and review of CAD drawings, including longitudinal (L-section) and cross-sectional (X-section) views, were conducted to ensure accuracy and alignment with the actual site dimensions. This process helped verify design conformity and identify any necessary adjustments during construction.

Drawing Analysis




Fig 32 : CAD drawing of Headpond

Office Work

- Analyzed survey data (layout)
- Prepared as-built drawings, Drafting & drawing tasks
- Surge tank level calculation , Turbine selection study , Energy output calculation
- Internship report Preparation.
- Project presentation preparation
- Academic poster design

Conclusion

This internship provided hands-on experience in hydroelectric project construction, enhancing our skills in structural work, quality control, and design verification. It bridged theoretical learning with practical application, equipping us with valuable insights for a career in civil engineering.

Cost Estimation

S.N.	Description	Amount (NPR)	Contingency (%)	Contingency Amount (NPR)	Tax/VAT (NPR)	Total Amount (NPR)
A	Pre-Operating	400,000,000.00	-	-	-	400,000,000.00
B	Civil Construction Works	3,059,330,618.90	5-7%	189,492,767.80	419,641,804.40	3,647,655,684.70
C	Hydromechanical Works	177,161,524.70	5%	8,858,076.20	16,702,295.50	202,721,896.50
D	Electromechanical Works	1,213,060,000.00	5%	60,653,000.00	19,105,695.00	1,292,818,695.00
E	Transmission Line & Interconnection	100,000,000.00	3%	3,000,000.00	13,390,000.00	116,390,000.00
F	Others	1,664,001,661.00	5%	120,295,782	96,710,250	1,881,007,693
Grand Total Cost with IDC	-	-	-	-	-	7,540,593,969.90
Project Cost per MW	-	-	-	-	-	200,547,712.00

References

- . Final DPR KAHEP Report pdf
- . <https://www.kel.com.np/>
- . <https://www.bpc.com.np/projects/kabeli-a-hydro-electric-project>
- . <https://www.bpc.com.np/group-companies/subsidiaries/kabeli-a-hydro-electric-project>

Annex




Fig 33 : Flow Duration Curve
Source: Final DPR KAHEP Report




Fig 34 : Catchment Area
Source: <https://projects.worldbank.org/en/projects-operations/project-detail/P122406>

Annex



Fig 35 : Location of Project




Fig 36 : Geological map

Thank you